

SECTION 12.03
SIDE MOUNTED SIGN FOUNDATION

12.03.01--Description: Work under this item shall consist of all necessary excavation including rock excavation, backfill, when necessary, and the construction of side mounted sign foundations conforming to the details shown on the plans.

12.03.02--Materials: Concrete shall be Class 'A' Concrete conforming to the pertinent requirements of Sections 6.01 and M.03.

Reinforcing steel shall conform to the pertinent requirements of Section M.06.01.

Stub post assemblies shall be steel conforming to ASTM A-36 and shall be galvanized after fabrication in accordance with ASTM 123.

All other material shall conform to the requirements shown on the plans.

12.03.03--Construction Methods : Excavation for the foundation shall conform to the neat lines as shown on the plans.

The concrete foundation shall be placed without forms except where unusual soil conditions prevent excavation to neat lines as shown on the plans. The forms shall be fastened in place before the placing of any concrete so that the resulting foundation will be monolithic.

The anchor bolts or stub post assembly and reinforcing steel shall be fabricated and preset as shown on the plans. After presetting the stub post, concrete shall be carefully placed and consolidated around the post.

12.03.04--Methods of Measurement: This work will be measured for payment by the number of units completely installed and accepted.

12.03.05--Basis of Payment: This work will be paid for at the Contract unit price each for "Side Mounted Sign Foundation," which price shall include all material, excavation including rock excavation, stub post assembly, breakaway coupling system, forms when necessary, labor and work incidental thereto.

Pay Item	Pay Unit
Side Mounted Sign Foundation	EA.