

**SECTION 18.07**  
**TEMPORARY IMPACT ATTENUATION SYSTEM**

**18.07.01--Description:** Work under this item shall consist of furnishing, installing, removing and when required, the relocation of a Temporary Impact Attenuation System of the type and size specified, in the locations shown on the plans or as directed by the Engineer.

**18.07.02--Materials:** Type A temporary systems shall conform to the material requirements of 18.02.02; other temporary systems shall conform to the material requirements for the impact attenuator shown on the plans or shall conform to the manufacturer's specifications..

**18.07.03--Construction Methods :** The temporary impact attenuator shall be installed as shown on the plans, as recommended by the manufacturer, or as directed by the Engineer. Each temporary impact attenuator shall be maintained by the Contractor during all stages of construction in accordance with the Provisions of 18.01.

The Contractor shall relocate the temporary impact attenuator to locations within the project limits as shown on the plans or as ordered by the Engineer.

The Contractor shall remove, at no cost to the State, all temporary impact attenuators that are no longer needed on the project.

**18.07.04--Method of Measurement:** This item will be measured for payment by the number of each temporary system installed in conformance with the plans and specifications and accepted by the Engineer. The relocation of temporary impact attenuators will be measured for payment each time they are satisfactorily moved to a new location as shown on the plans or directed by the Engineer. Any system realignment at the site specified shall not be paid for as relocation. Relocation is defined as moving the complete system.

**18.07.05--Basis of Payment:** This item shall be paid for at the Contract unit price for each "Temporary Impact Attenuation Systems" of the size and type specified, complete in place which shall include materials, equipment, transportation, tools and labor incidental thereto.

The relocation of the temporary impact attenuation systems will be paid for at the contract unit price each for relocation of Temporary Impact Attenuation Systems of the size and type specified, which shall include transportation, materials, equipment, tools and labor incidental thereto.

Pay Item	Pay Unit
Temporary Impact Attenuation System (Type) (Size)	EA.
Relocation of Temporary Impact Attenuation System (Type) (Size)	EA.