

SECTION 5.13
POLYVINYL CHLORIDE PLASTIC PIPE

5.13.01--Description: This item shall consist of furnishing and installing polyvinyl chloride pipe for use as drains through the concrete bridge slab where shown on the plans or as ordered by the Engineer.

5.13.02--Materials: The pipe shall conform to the requirements of Subarticle M.08.01-27 and shall be schedule 40.

5.13.03--Construction Methods : The pipe drain shall be placed through the concrete slab at locations shown and as indicated on the plans. Pipe shall be secured at the proper locations before placing concrete. Where required, couplings and elbows may be used. After placing of the concrete slab, the pipe end shall be trimmed flush with the top surface of the concrete slab.

5.13.04--Method of Measurement: This work will be measured for payment by the number of meters of pipe completed and accepted in place and measured through all fittings.

5.13.05--Basis of Payment: This work will be paid for at the contract unit price per meter for "Polyvinyl Chloride Plastic Pipe", of the type specified, complete in place, which price shall include all materials, fittings, equipment, tools, labor and work incidental thereto.

Pay Item	Pay Unit
(size) Polyvinyl Chloride Plastic Pipe	m