

SECTION 6.09
REPOINTED MASONRY

6.09.01--Description: This item shall consist of repointing existing masonry walls where indicated on the plans or as directed, in accordance with these specifications.

6.09.02--Materials: The mortar for this work shall conform, as regards materials, proportions and mixing, to the pointing mortar specified in Article M.11.04.

6.09.03--Construction Methods : Pointing shall not be done in freezing weather or when the stone contains frost. The joints in the existing masonry shall be thoroughly raked out and cleaned of all loose mortar, dirt, or other foreign material to a depth of about 50 mm or as ordered. The joints shall be thoroughly wet with water and filled with mortar. The mortar shall be well driven into the joints and finished with an approved pointing tool. The wall shall be kept wet while pointing is being done; and in hot or dry weather, the pointed masonry shall be protected from the sun and kept wet for a period of at least three days after completion.

After the pointing is completed and the mortar set, the wall shall be thoroughly cleaned and left in a neat and workmanlike condition.

6.09.04--Method of Measurement: The quantity of repointed masonry shall be the actual number of square meters completed and accepted within the neat lines as shown on the plans or as ordered.

6.09.05--Basis of Payment: This work will be paid for at the contract unit price per square meter for "Repointed Masonry" which price shall include all materials, equipment, tools and labor incidental thereto.

Pay Item	Pay Unit
Repointed Masonry	m ²