

SECTION 8.14
RESET STONE CURBING

8.14.01--Description: This work shall consist of the removing and resetting or adjusting of existing stone curbing to the lines and grades given, in accordance with the dimensions and details of the plans or as ordered and in conformity with these specifications.

8.14.02--Materials: All existing curbing which is acceptable shall be used. The reset stone curbing shall be in lengths of not less than 1.2 m, except where necessary for closures, where no piece shall be less than 1 m in length. Mortar for this work shall conform, as regards materials, proportions and mixing, to the mortar specified in Article M.11.04.

8.14.03--Construction Methods: The construction methods for this work shall conform to the requirements of Article 8.13.03 for stone curbing, as supplemented by the following requirements:

The curbing to be reset shall be removed with care to avoid damage and, if ordered, shall be transported to a point or points on the project which will allow all the reset curbing to be installed in continuous lines. Curbing removed and not reset shall remain the property of the State unless otherwise ordered by the Engineer and shall be transported to such points, adjacent to the work, as the Engineer may designate. Where adjustments only have to be made to curbing, such adjustments shall be carried out as specified by the Engineer.

8.14.04--Method of Measurement: This work will be measured for payment by the actual number of meters of the class of curbing, reset and accepted.

8.14.05--Basis of Payment: Payment for this work will be made as follows:

This work will be paid for at the contract unit price per meter for "Reset Curbing," complete in place, which price shall include all materials, equipment, tools and labor incidental thereto and all excavation, backfilling, disposal of surplus material and all drainage openings.

There will be no direct payment for furnishing, placing and compacting granular base, beveling or rounding the ends of the curbing, sealing the joints with mortar, removing the curbing and hauling it to any location on or adjacent to the project as directed by the Engineer; but the cost of this work shall be considered as included in the general cost of the work.

| Pay Item | Pay Unit |
|---------------------------|----------|
| Reset Curbing (Type-Size) | m |