

**State of Connecticut**

**Department of Transportation**

**SUPPLEMENTAL SPECIFICATIONS**

**TO**

**THE STANDARD SPECIFICATIONS**

**FOR**

**ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION**

*FORM 816*

**2004**

**JULY 2006**

**JULY 2006**

**DIVISION I**  
**GENERAL REQUIREMENTS AND COVENANTS**

<u>SECTION</u>		<u>SPECIFICATION NUMBER</u>
1.01	Definition of Terms and Permissible Abbreviations	101
1.09	Measurement and Payment	109
1.20	General Clauses for Facilities Construction	120

July 2006

**DIVISION II**  
**CONSTRUCTION DETAILS**

<u>SECTION</u>		<u>SPECIFICATION NUMBER</u>
3.04	Processed Aggregate Base	304
4.01	Concrete Pavement	401
6.01	Concrete for Structures	601
6.03	Structural Steel	603
6.12	Concrete Cylinder Curing Box	612
7.02	Piles	702
9.10	Metal Beam Rail	910
9.18	Three-Cable Guide Railing (I-Beam Post) and Anchorages	918
10.10	Concrete Handhole	1010
11.13	Control Cable	1113

July 2006

**DIVISION III**  
**MATERIALS SECTION**

**SECTION**

**SPECIFICATION  
NUMBER**

M.16 Traffic Control Signals  
M.17 Elastomeric Materials  
M.18 Signing

M16  
M17  
M18

**July 2006**  
**STANDARD SPECIFICATIONS**  
**FOR**  
**ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION**  
**FORM 816**

**ERRATA**

<u>PG.</u>	<u>ARTICLE OR SUBARTICLE</u>	<u>LINE NO.</u>	<u>CORRECTION</u>
iv	Table of Contents	11	Change "Guild" to "Guide"
4	1.01.01	8	After the end of the definition for "Plans," insert as a subset, "A. Standard Sheets – Standardized plans containing details approved by the Department and the FHWA, for construction of a given type on any project, included in contracts on an as-needed basis."
6	1.01.02	41	Change "Aluminum Association" to "Aluminum Association, Inc. (The)"
6	1.01.02	42	Delete "AAA – Aluminum Alloy Association"
7	1.01.02	1	Insert "AABC – Associated Air Balance Council"
7	1.01.02	1	Insert "AAMA – American Architectural Manufacturers Association"
7	1.01.02	12	Insert "ABMA – American Bearing Manufacturers Association"
7	1.01.02	12	Insert "ACGIH – American Council of Government Industrial Hygienists"
7	1.01.02	12	Change "American Concrete Institute" to "ACI International (American Concrete Institute)"
7	1.01.02	14	Insert "ADAAG – Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities"
7	1.01.02	16	Change "Associated General Contractors of America" to "Associated General Contractors of America (The)"
7	1.01.02	19	Insert "AI – Asphalt Institute"
7	1.01.02	19	Change "American Institute of Architects" to "American Institute of Architects (The)"
7	1.01.02	20	Delete "AIEE – American Institute of Electrical Engineers "
7	1.01.02	24	Delete "ALI – Associated Laboratories, Inc."
7	1.01.02	26	Change "American Lumber Standard Committee" to "American Lumber Standards Committee, Incorporated"
7	1.01.02	27	Change "Air Movement and Control Association" to "Air Movement and Control Association International, Inc."
7	1.01.02	31	Delete "AOEC – Area of Environmental Concern"
7	1.01.02	33	Change "The Engineered Wood Association" to "APA-The Engineered Wood Association"
7	1.01.02	37	Change "Air Conditioning" to "Air-Conditioning"
8	1.01.02	7	Change "Air Conditioning" to "Air-Conditioning"
8	1.01.02	8	Change "American Society of Mechanical Engineers" to "ASME International (The American Society of Mechanical Engineers International)"
8	1.01.02	18	Delete "ATA – American Transit Association"
8	1.01.02	20	Delete "AWG – American Wire Gauge"
8	1.01.02	22	Change "Wood-Preservers" to "Wood-Preservers' "
8	1.01.02	33	Delete "AZI – American Zinc Institute"
8	1.01.02	35	Change "Building Officials and Code Administrators International" to "BOCA International, Inc."

<u>PG.</u>	<u>ARTICLE OR SUBARTICLE</u>	<u>LINE NO.</u>	<u>CORRECTION</u>
8	1.01.02	38	Change "Library" to "Laboratory"
9	1.01.02	2	Change "CONNDOT" to "ConnDOT"
9	1.01.02	6	Delete "CPI – Clay Pipe Institute"
9	1.01.02	9	Delete "CS – Commercial Standard"
9	1.01.02	10	Change "Construction Specifications Institute" to "Construction Specifications Institute (The)"
9	1.01.02	12	Change "Tower" to "Technology"
9	1.01.02	17	Delete "DFPA – Douglas Fir Plywood Association"
9	1.01.02	19	Change "Department of Defense" to "Department of Defense Military Specifications and Standards"
9	1.01.02	21	Change "Association" to "Alliance"
9	1.01.02	23	Delete "U.S. Department of Transportation"
9	1.01.02	28	Delete "U.S. Department of Transportation"
9	1.01.02	30	Insert "FMG – FM Global"
9	1.01.02	31	Delete "U.S. Department of Transportation"
10	1.01.02	2	Delete "HASP – Health and Safety Plan"
10	1.01.02	3	Delete "HMA – Hot Mix Asphalt or Bituminous Concrete"
10	1.01.02	4	Delete "HPMA – Hardwood Plywood Manufacturers Association"
10	1.01.02	5	Insert "HPVA – Hardwood Plywood & Veneer Association"
10	1.01.02	9	Insert "ICC – International Code Council"
10	1.01.02	9	Change "Insulated Cable Engineers Association" to "Insulated Cable Engineers Association, Inc."
10	1.01.02	10	Change "Institute of Electrical and Electronics Engineers" to "Institute of Electrical and Electronics Engineers, Inc. (The)"
10	1.01.02	21	Change "Military Standardization Documents, U.S. Department of Defense" to "(MILSPEC) Military Specification and Standards"
10	1.01.02	24	Delete "MS – Military Specifications"
10	1.01.02	26	Change "Manufacturers Standardization Society of the Valve and Fittings Industry Inc." to "Manufacturers Standardization Society of The Valve and Fittings the Valve Industry Inc."
10	1.01.02	29	Change "National Association of Architectural Metal Manufacturers (The)" to "National Association of Architectural Metal Manufacturers"
10	1.01.02	31	Insert "NADCA – National Air Duct Cleaners Association"
10	1.01.02	34	Delete "NBS – National Bureau of Standards"
10	1.01.02	35	Delete "NC – National Course"
11	1.01.02	3	Delete "NCPRC – National Clay Pipe Research Corporation"
11	1.01.02	10	Change "International Electrical Testing Association" to "InterNational Testing Association"
11	1.01.02	12	Delete "NFS – NFS International"
11	1.01.02	13	Insert "NHLA – National Hardwood Lumber Association"
11	1.01.02	18	Insert "NLGA – National Lumber Grades Authority"
11	1.01.02	18	Delete "NLMA – National Lumber Manufacturers Association"
11	1.01.02	21	Insert "NSF – NSF International"
11	1.01.02	21	Change "National Terrazzo and Mosaic Association (The)" to "National Terrazzo and Mosaic Association, Inc."
11	1.01.02	26	Delete "PCC – Portland Cement Concrete"
11	1.01.02	28	Delete "PLP – Plastic Laminate Producers"
11	1.01.02	29	Delete "PS – Product Standard of NBS, U.S. Department of Commerce"
11	1.01.02	32	Delete "RLMI – Reflector and Lamp Manufacturers' Institute"

<u>PG.</u>	<u>ARTICLE OR SUBARTICLE</u>	<u>LINE NO.</u>	<u>CORRECTION</u>
11	1.01.02	35	Delete "SAWP – Society of American Wood Preservers"
11	1.01.02	36	Insert "SDI – Steel Deck Institute"
11	1.01.02	36	Insert "S.D.I. – Steel Door Institute"
11	1.01.02	37	Insert "SJI – Steel Joist Institute"
11	1.01.02	37	Insert "SMACNA – Sheet Metal and Air Conditioning Contractors' National Association"
11	1.01.02	37	Change "Southern Pine Inspection Bureau" to "Southern Pine Inspection Bureau (The)"
12	1.01.02	9	Change "Tile Council of America" to "Tile Council of America, Inc."
12	1.01.02	10	Insert "TIA – Telecommunications Industry Association"
12	1.01.02	10	Insert "TPI – Truss Plate Institute, Inc."
12	1.01.02	10	Delete "UBC – Uniform Building Code"
12	1.01.02	11	Change "Underwriters Laboratories, Inc." to "Underwriters Laboratories Inc."
12	1.01.02	12	Delete "UMTA – Urban Mass Transportation Administration, U.S. Department of Transportation"
12	1.01.02	14	Delete "UPC – Uniform Plumbing Code"
12	1.01.02	15	Insert "USGBC – U.S. Green Building Council"
12	1.01.02	16	Delete "USS – United States Standard"
12	1.01.02	17	Delete "VOC – Volatile Synthetic Organic Chemicals"
12	1.01.02	19	Delete "WCLA – West Coast Lumberman's Association"
12	1.01.02	20	Insert "WCSC – Window Covering Safety Council"
12	1.01.02	20	Delete "WSA – Temporary Waste Stockpile Area"
12	1.01.03	31	Insert "AOEC – Area of Environmental Concern"
12	1.01.03	31	Insert "AWG – American Wire Gauge"
13	1.01.03	16	Insert "HASP – Health and Safety Plan"
13	1.01.03	29	Insert "PCC – Portland Cement Concrete"
14	1.01.03	25	Insert "VOC – Volatile Organic Compound"
14	1.01.03	26	Insert "WSA – Temporary Waste Stockpile Area"
22	1.03.07	23	Change "\$1,000,000" to "\$2,000,000"
32	1.05.01	38	Change "Connecticut General Statutes" to "CGS"
45	1.05.15	29	Change "Department of Public Utility Control" to "DPUC"
105	1.20	29	Change "Workmen and Equipment" to "Personnel and Equipment"
105	1.20	31	Delete "Completion of Construction Work and"
107	1.20-1.02.13	15	Change "Americans with Disabilities Act Accessibility Guidelines" to "ADAAG"
131	1.20-1.08.05	34	Change "Workmen and Equipment" to "Personnel and Equipment"
133	1.20-1.08.13	7	Delete "Completion of Construction Work and"
245	4.06.04	11	Change " <b>Over weight (mass) Adjustments -</b> " and replace with indented "Over weight (mass) Adjustments -" as a subsection of " <b>1. Bituminous Concrete Class ( )</b> ".
351	6.03.03	8	Change "MS MIL-C-11796B" to "MIL-C-11796B"
496	9.70.01	37	Change "CDOT" to "ConnDOT"
604	18.00.02	7	Change "National Cooperative Highway Research Program (NCHRP)" to "NCHRP"
623	M.03.01	9	Change "Cement and Concrete Reference Laboratory" to "CCRL"
623	M.03.01	13	Change "Cement and Concrete Reference Laboratory" to "CCRL"
626	M.03.01	2	Change "Cement and Concrete Reference Laboratory" to "CCRL"
626	M.03.01	3	Change "NBS" to "NIST"

<u>PG.</u>	<u>ARTICLE OR SUBARTICLE</u>	<u>LINE NO.</u>	<u>CORRECTION</u>
632	M.03.01	18	Change "Cement and Concrete Reference Laboratory" to "CCRL"
638	M.04.02	37	Change "Asphalt Institute's" to "AI's"
735	M.13.03	22	Change "AOAC International" to "AOAC"
760	M.15.15	21	Change "non-fusible" to "fused"
780	M.16.08	41	Change "Americans With Disabilities Act (ADA)" to "ADA"
790	M.16.10	24	Change "Underwriter's Laboratory" to "UL"
800	M.17.01	19	Change "AAA 6061-T6" to "AA 6061-T6"
845	Index	6	Add page 133 to "Acceptance of Project"
846	Index	13	Add page 107 to "Bids: Consideration of"
847	Index	28	Add page 132 to "Cleaning Up, Final"
849	Index	25	Add page 107 to "Consideration of Bids"
849	Index	39	Add page 108 to "Contract: Intent of"
850	Index	3	Add page 133 to "Contractor's: Responsibility, Termination of the"
850	Index	13	Add page 114 to "Cooperation by Contractor"
850	Index	15	Add page 114 to "Coordination of Special Provisions, Plans, Supplemental Specifications and Standard Specifications and Other Contract Requirements"
850	Index	40	Add page 128 to "Cutting and Patching:"
852	Index	16	Add page 106 to "Examination of Plans, Specifications, Special Provisions and Site of Work"
852	Index	38	Insert "Facilities, Temporary...126"
853	Index	7	Add page 132 to "Final: Cleaning Up"
854	Index	35	Add page 115 to "Inspection"
855	Index	11	Add page 108 to "Intent of Contract"
855	Index	22	Add page 106 to "Knowledge of Applicable Laws"
855	Index	25	Add page 106 to "Laws: Knowledge of Applicable"
856	Index	27	Add page 120 to "Materials: Source of Supply and Quality"
856	Index	28	Add page 121 to "Materials: Storage of"
857	Index	33	Add page 133 to "Operation and Maintenance Manuals:"
857	Index	34	Change page 133 to 136 for "Equipment and Systems Maintenance Manual"
859	Index	2	Add page 131 to "Personnel and Equipment"
860	Index	6	Add page 114 to "Plans: Coordination of Special Provisions, Supplemental Specifications and Standard Specifications and Other Contract Requirements"
860	Index	7	Add page 106 to "Plans: Examination of"
860	Index	30	Change page 108 to 112 for "Product Data"
860	Index	31	Change page 108 to 112 for "Product Samples "
860	Index	32	Add page 124 to "Product Selection:"
861	Index	12	Add page 126 to "Prosecution of Work"
861	Index	38	Change page 115 to 135 for "Record Drawings"
863	Index	3	Add page 125 to "Sanitary Provisions"
863	Index	18	Insert "Services, Temporary...126"
863	Index	23	Add page 111 to "Shop Drawings"
864	Index	4	Add page 106 to "Site of Work, Examination of"
864	Index	12	Add page 120 to "Source of Supply and Quality"
864	Index	19	Add page 114 to "Special Provisions: Coordination of Plans, Supplemental Specifications and Standard Specifications and Other Contract Requirements"
864	Index	20	Add page 106 to "Special Provisions: Examination of"



<u>PG.</u>	<u>ARTICLE OR SUBARTICLE</u>	<u>LINE NO.</u>	<u>CORRECTION</u>
864	Index	26	Add page 114 to "Specifications: Coordination of Plans, Special Provisions and Other Contract Requirements"
864	Index	27	Add page 106 to "Specifications: Examination of"
864	Index	43	Add page 121 to "Storage"
865	Index	27	Delete page 108 from "Submittals: Shop Drawings"
865	Index	45	Insert "Temporary Utilities, Services, and Facilities...126"
866	Index	2	Add page 133 to "Termination of Contractor's Responsibility"
866	Index	23	Insert "Training...137"
866	Index	45	Add page 133 to "Utility Services"
867	Index	8	Insert "Warranties...121"
867	Index	24	Add page 126 to "Work: Prosecution of"

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 1.01  
DEFINITIONS OF TERMS AND  
PERMISSIBLE ABBREVIATIONS**

**1.01.02 — Abbreviations, Publications, and Standards:**

*Delete the like-named abbreviations and replace it with the following abbreviations:*

“**AA** – Aluminum Association, Inc. (The)  
**ALSC** – American Lumber Standard Committee, Incorporated  
**AMCA** – Air Movement and Control Association International, Inc.  
**AOSA** – Association of Official Seed Analysts, Inc.  
**ASME** – ASME International (The American Society of Mechanical Engineers International)  
**CTI** – Cooling Technology Institute  
**EIA** – Electronic Industries Alliance  
**ICEA** – Insulated Cable Engineers Association, Inc.  
**IEEE** – Institute of Electrical and Electronics Engineers, Inc. (The)  
**NTMA** – National Terrazzo & Mosaic Association, Inc. (The)  
**TCA** – Tile Council of America, Inc.”

*Delete the Following abbreviations:*

“**ADA** – Americans with Disabilities Act  
**AFPA** – American Forest and Paper Association  
**BOCA** – Building Officials and Code Administrators International  
**FM** – Factory Mutual System  
**ICBO** – International Conference of Building Officials  
**MIL** – Military Standardization Documents, U.S Department of Defense  
**MS** – Military Specifications  
**NWWDA** – National Wood Window and Door Association  
**NFS** – NFS International”

*Add the following abbreviations:*

“**ADAAG** – Americans with Disabilities Act (ADA)  
**AABC** – Associated Air Balance Council  
**AAMA** – American Architectural Manufacturers Association  
**ABMA** – American Bearing Manufacturers Association  
**AF&PA** – American Forest & Paper Association  
**AI** – Asphalt Institute  
**BIA** – Brick Industry Association (The)  
**CDA** – Copper Development Association Inc.

**CGA** – Compressed Gas Association  
**FMG** – FM Global  
**HI** – Hydraulic Institute  
**HPVA** – Hardwood Plywood & Veneer Association  
**ICC** – International Code Council  
**ICC-ES** – ICC Evaluation Service, Inc.  
**IEC** – International Electrotechnical Commission  
**IGMA** – Insulating Glass Manufacturers Alliance  
**ISO** – International Organization for Standardization  
**MILSPEC** – Military Specification and Standards  
**NADCA** – National Air Duct Cleaners Association  
**NFRC** – National Fenestration Rating Council  
**NHLA** – National Hardwood Lumber Association  
**NSF** – NSF International (National Sanitation Foundation International)  
**PDI** – Plumbing & Drainage Institute  
**SDI** – Steel Deck Institute *or*  
    - Steel Door Institute  
**SJI** – Steel Joist Institute  
**SMACNA** – Sheet Metal and Air Conditioning Contractors' National Association  
**SPRI** – Single Ply Roofing Industry  
**SWRI** – Sealant, Waterproofing, & Restoration Institute  
**TIA/EIA** – Telecommunications Industry Association/Electronic Industries Alliance  
**TRB** – Transportation Research Board  
**UFAS** – Uniform Federal Accessibility Standards  
**USGBC** – U.S. Green Building Council  
**WDMA** – Window & Door Manufacturers Association”

CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 1.09  
MEASUREMENT AND PAYMENT

**Article 1.09.04 – Extra and Cost-Plus Work**

*Delete the word “bonding” under section (a) Labor, (3).*

*Change Section designation for Miscellaneous from:*

**(f) Miscellaneous** to: **(g) Miscellaneous**

*Add the following as (f):*

**(f) Bonding Costs:** For bonding on the total cost of the cost-plus work including administrative expenses as outlined in (e) above, the Contractor shall receive its actual cost. The Contractor shall provide to the Engineer documentation, satisfactory to the Engineer in form and substance, of all such costs.

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 1.20  
GENERAL CLAUSES FOR FACILITIES CONSTRUCTION**

**1.20-1.02.04 – Examination of Plans, Specifications, Special Provisions and Site of Work:**

*Delete the first sentence of the first paragraph and replace with the following:*

“CSI-formatted specifications are organized into Divisions and Sections based on the CSI’s “MasterFormat” numbering system.”

**1.20-1.02.13 – Knowledge of Applicable Laws:**

*Delete Items 1 through 9 in their entirety and replace with the following:*

1. “The 2003 International Building Code with the State Building Code, including latest Connecticut Supplement.
2. The 2003 International Plumbing Code.
3. The 2003 International Mechanical Code.
4. The 2003 International Existing Building Code.
5. The 2003 International Energy Conservation Code.
6. The 2005 NFPA 70 National Electrical Code.
7. The 2003 ICC/ANSI A117.1.
8. The Fire Safety Code, including latest Connecticut Supplement.
9. The 2003 International Fire Code.
10. The 2003 NFPA 1 Uniform Fire Code.
11. The 2003 NFPA 101 Life Safety Code.”

**1.20-1.05.02--Shop Drawings, Product Data, Product Samples and Quality Assurance Submittals**

*In column B of line 001, line 001a, and line 001b of the table in subsection 1, replace “07511” with “075110.”*

*Add the following to the end of the first paragraph of subsection 2:*

“The Department reserves the right to return partial submittals unreviewed to the Contractor.”

*Revise the third paragraph of subsection 2 to read:*

“The Contractor shall allow at least 60 calendar days for review of any submittal requiring approval by FAA, FTA, any railroad, DEP, U.S. Coast Guard, Army Corps of Engineers, or any other outside agency.”

*Replace the first sentence of the first paragraph of subsection 4 with the following:*

“Shop Drawings consist of fabrication and installation drawings, roughing-in and setting drawings, schedules, patterns, templates and similar drawings, and wiring diagrams showing field-installed wiring, including power, signal, and control wiring.”

*Replace the first sentence of the second paragraph of subsection 4 with the following:*

“Shop drawings shall include the following information: Contract number, Project description, number and title of the drawing, date of drawing, revision number, name of Contractor and subcontractor submitting drawings, dimensions, identification of products, shopwork manufacturing instructions, design calculations, statement of compliance with Contractual standards, notation of dimensions established by field measurement, relationship to adjoining construction clearly indicated, seal and signature of a professional engineer if specified, and any other information required by individual Contract provisions.”

*Replace the first sentence of the first paragraph of subsection 5 with the following:*

“Product data consists of printed information such as manufacturer’s product specifications, manufacturer’s installation instructions, manufacturer’s catalog cuts, standard color charts, wiring diagrams showing factory-installed wiring, printed performance curves, operational range diagrams, and mill reports.”

*Replace the first sentence of the first paragraph of subsection 7 with the following:*

“Quality assurance submittals consist of qualification data, design data, certifications, manufacturer’s instructions, manufacturer’s field reports, test reports, Material Safety Data Sheets (MSDSs), and other quality assurance information required by individual Contract provisions.”

#### **1.20-1.05.24--Project Meetings:**

*Delete the third paragraph under subsection 1 and replace with the following:*

“The meeting participants will discuss items of significance that could affect progress, including tentative construction schedule; phasing; critical work sequencing and long-lead items; designation of key personnel and their duties; procedures for processing field decisions and construction orders; procedures for requests for interpretation; procedures for testing and inspecting; procedures for processing applications for payment; distribution of Contract documents; submittals; LEED (Leadership in Energy and Environmental Design) requirements; preparation of record documents; use of the premises and existing building; work restrictions; Owner’s occupancy requirements; responsibility for temporary facilities and controls; construction waste management and recycling; parking availability; office, work, and storage areas; equipment deliveries and priorities; safety procedures; first aid; security; housekeeping; and working hours.”

*Delete the second paragraph under subsection 2 and replace with the following:*

“The meeting participants shall review progress of other construction activities and preparations for the particular activity under consideration, including requirements of Contract documents, related requests for interpretations, related construction orders, purchases, deliveries, submittals, review of mockups, possible conflicts, compatibility problems, time schedules, weather limitations, manufacturer’s written recommendations, warranty requirements, compatibility of materials, acceptability of substrates, temporary facilities and controls, space and access limitations, regulations of authorities having jurisdiction, testing and inspecting requirements, installation procedures coordination with other work, required performance results, protection of adjacent work, and protection of construction and personnel.”

*Delete the end of the fourth paragraph under subsection 3 beginning with “(8)” and replace with the following:*

“(8) review the present and future needs of each entity represented at the meeting, including such items as interface requirements, time, sequences, deliveries, off-site fabrication problems, access, site utilization, temporary facilities and controls, hours of work, hazards and risks, housekeeping, quality and work standards, status of correction of deficient items, field observations, requests for interpretations, status of proposal requests, pending changes, status of construction orders, and documentation of information for payment requests.”

#### **1.20-1.05.25—Schedules and Reports:**

*Add the following to the end of subsection 1:*

“The Contractor shall provide the Engineer with a copy of the software used to prepare the construction schedule. This software will be loaded on a computer in the Engineer’s field office. The software will remain the property of the Contractor.”

#### **1.20-1.08.03—Prosecution of Work:**

*Under subsection '3. Cutting and Patching,' delete the heading 'B. Protection of Structural Elements' and replace with the following:*

**"B. Protection:"**

*Move the existing first and second paragraphs to under the following subparagraph:*

"1. Structural Elements:"

*Add the following after the first paragraph under B:*

"2. Operational Elements: The Contractor shall not cut and patch operating elements and related components in a manner that results in their reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.

3. Miscellaneous Elements: The Contractor shall not cut and patch miscellaneous elements or related components in a manner that could change their load-carrying capacity, that results reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety."

*Add the following after subsection 3:*

**"4. Selective Demolition:**

**A. Definitions:**

**Remove:** The Contractor shall detach materials from existing construction and legally dispose or recycle them off-site, unless indicated to be removed and salvaged or removed and reinstalled. Except for materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Engineer's property, demolished materials shall become Contractor's property and shall be removed from the Project Site.

**Remove and Salvage:** The Contractor shall detach materials from existing construction and deliver them to Engineer. The Engineer reserves the right to identify other materials for salvage during the course of demolition.

**Remove and Reinstall:** The Contractor shall detach materials from existing construction, prepare them for reuse, and reinstall them where indicated.

**Existing to Remain:** Existing materials of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.



## **B. Approval Process:**

The Contractor shall submit pre-demolition photographs to the Engineer prior to the commencement of Project work to show existing conditions of adjoining construction and site improvements, including finish surfaces, that might be misconstrued as damage caused by selective demolition operations.

Well in advance of performing any selective demolition on the Project, the Contractor shall submit to the Engineer a proposal describing the procedures that the Contractor intends to use for same.

The Contractor shall include the following information, as applicable, in its proposal: (1) detailed sequence of selective demolition and removal work with starting and ending dates for each activity while ensuring that the Engineer's on-site operations are not disrupted; (2) interruption of utility services; (3) coordination for shutoff, capping, and continuation of utility services; (4) use of elevators and stairs; (5) locations of temporary partitions and means of egress; (6) coordination of Engineer's continuing occupancy of portions of existing building and of Engineer's partial occupancy of completed Project work; and (7) means of protection for items to remain and items in path of waste removal from building.

The Contractor shall comply with (1) governing EPA notification regulations before beginning selective demolition; (2) hauling and disposal regulations of authorities having jurisdiction; (3) ANSI A10.6; and (4) NFPA 241.

The Engineer will conduct a Pre-Demolition Meeting at the Project site in accordance with Article 1.20-1.05.24. Said meeting will review the methods and procedures related to selective demolition including, but not limited to, the following: (1) an inspection and discussion of the condition of construction to be selectively demolished; (2) a review of the structural load limitations of the existing structure; (3) a review and finalization of the selective demolition schedule and a verification of the availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays; (4) a review of requirements of Project work performed by other trades that rely on substrates exposed by selective demolition operations; and (5) a review of areas where existing construction is to remain and requires protection.

## **C. Repair Materials:**

The Contractor shall comply with Article 1.20-1.08.03 subsection 3E for repair materials and shall comply with material and installation requirements specified in other Contract provisions.

## **D. Examination:**

The Contractor shall (1) verify that utilities have been disconnected and capped; (2) survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required; (3) inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged; (4) investigate and measure the nature and extent of unanticipated mechanical, electrical, or structural elements that conflict with intended function or design and submit a written report to Engineer; and (5) perform surveys as the Project work progresses to detect hazards resulting from selective demolition activities.

#### **E. Utility Services:**

The Contractor shall (1) maintain existing utility services indicated to remain and protect them against damage during selective demolition operations; (2) not interrupt existing utilities serving occupied or operating facilities unless authorized in writing by the Engineer; (3) provide temporary services during interruptions to existing utilities, as acceptable to Engineer; (4) provide at least 3 calendar days notice to the Engineer if shutdown of service is required during changeover; and (5) locate, identify, disconnect, and seal or cap off indicated utilities serving areas to be selectively demolished. The Contractor shall arrange to shut off indicated utilities with utility companies. If utility services are required to be removed, relocated, or abandoned, before proceeding with selective demolition the Contractor shall provide temporary utilities that bypass area of selective demolition and that maintain continuity of service to other parts of building. The Contractor shall cut off pipe or conduit in walls or partitions to be removed and shall cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing.

The Contractor shall refer to other Contract provisions for shutting off, disconnecting, removing, and sealing or capping utilities. The Contractor shall not start selective demolition work until utility disconnecting and sealing have been completed and verified by the Engineer in writing.

#### **F. Preparation:**

The Contractor shall conduct selective demolition and debris-removal operations to ensure minimum interference with adjacent occupied and used facilities on the Project site. The Contractor shall not disrupt the Owner's operations without the Engineer's permission. The Contractor shall protect existing site improvements, appurtenances, and landscaping to remain.

The Contractor shall provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain. The Contractor shall provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas. The Contractor shall protect walls, ceilings, floors, and other existing finish work that are to remain or that are

exposed during selective demolition operations. The Contractor shall cover and protect furniture, furnishings, and equipment that have not been removed.

The Contractor shall provide temporary enclosures for protection of existing building and construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. The Contractor shall provide temporary weathertight enclosure for building exterior. Where heating is needed and permanent enclosure is not complete, the Contractor shall provide insulated temporary enclosures and shall coordinate enclosure with ventilating and material drying or curing requirements to avoid dangerous conditions and effects.

The Contractor shall erect and maintain dustproof partitions and temporary enclosures to limit dust and dirt migration and to separate areas from fumes and noise.

The Contractor shall provide and maintain interior and exterior shoring, bracing, or structural support to preserve stability and prevent movement, settlement, or collapse of construction to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished. The Contractor shall strengthen or add new supports when required during progress of selective demolition.

#### **G. Pollution Controls:**

The Contractor shall comply with governing regulations pertaining to environmental protection.

The Contractor shall not use water when it may create a hazardous or objectionable condition such as ice, flooding, or pollution.

The Contractor shall remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas. The Contractor shall remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.

The Contractor shall clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. The Contractor shall return adjacent areas to condition existing before selective demolition operations began.

#### **H. Performance:**

The Contractor shall not use explosives for demolition purposes.

The Contractor shall demolish and remove existing construction only to the extent required by new construction and as indicated. The Contractor shall (1) proceed with selective demolition systematically; (2) neatly cut openings and holes plumb, square, and true to dimensions required; (3) use cutting methods least likely to damage

remaining or adjoining construction; (4) use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces; (5) temporarily cover openings to remain; (6) cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces; (7) not use cutting torches until work area is cleared of flammable materials; (8) verify condition and contents of concealed spaces such as duct and pipe interiors before starting flame-cutting operations; (9) maintain fire watch and portable fire-suppression devices during flame-cutting operations; (10) maintain adequate ventilation when using cutting torches; (11) remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site; (12) remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation; (13) locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing; and (14) dispose of demolished items and materials promptly.

The Contractor shall comply with the Engineer's requirements for using and protecting walkways, building entries, and other building facilities during selective demolition operations.

The Contractor shall demolish and remove foundations and other below grade structures completely unless otherwise indicated on the plans. The Contractor shall fill below grade areas and voids resulting from demolition of structures with granular fill materials. Prior to placement of fill materials, the Contractor shall ensure that the areas to be filled are free of standing water, frost, frozen material, trash, and debris. After fill placement and compaction, grade surface to meet adjacent contours and provide flow to surface drainage structures. Backfilling and grading related to demolition is included in the Major Lump Sum Item (MLSI) for the Project. There will be no separate payment for this backfilling and grading.

The Contractor shall (1) demolish concrete in sections; (2) cut concrete at junctures with construction to remain to the depth shown on the Contract plans and at regular intervals using power-driven saw; and (3) remove concrete between saw cuts.

The Contractor shall (1) demolish masonry in small sections; (2) cut masonry at junctures with construction to remain using power-driven saw; and (3) remove masonry between saw cuts.

The Contractor shall (1) saw-cut perimeter of concrete slabs-on-grade to be demolished as shown on the Contract plans; and (2) break up and remove concrete slabs-on-grade.

The Contractor shall (1) remove floor coverings and adhesive according to recommendations in RFCI-WP and its Addendum; and (2) remove residual adhesive and prepare substrate for new floor coverings by one of the methods recommended by RFCI.

The Contractor shall (1) only remove existing roofing in one day to the extent that it can be covered by new roofing; and (2) refer to other Contract provisions for new roofing requirements.

The Contractor shall remove air conditioning equipment without releasing refrigerants.

#### **I. Reuse of Building Elements:**

The Contractor shall not demolish building elements beyond what is indicated on the plans without the Engineer's approval.

#### **J. Removed and Salvaged Materials:**

Unless otherwise directed by the Engineer, the Contractor shall (1) store materials in a secure area until delivery to the owner; (2) transport materials to the owner's storage area off-site; and (3) protect materials from damage during transport and storage.

#### **K. Removed and Reinstalled Materials:**

Unless otherwise directed by the Engineer, the Contractor shall (1) clean and repair materials to functional condition adequate for intended reuse; (2) paint equipment to match the color of new equipment; (3) protect materials from damage during transport and storage; and (4) reinstall items in locations indicated complying with installation requirements for new materials and equipment and providing connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

#### **L. Existing Materials to Remain:**

The Contractor shall protect construction indicated to remain against damage and soiling during selective demolition.

The Contractor shall drain piping and cap or plug piping with the same or a compatible piping material for piping to be abandoned in place.

The Contractor shall cap or plug ducts with the same or a compatible ductwork material for ducts to be abandoned in place.

The Contractor shall cut and remove concealed conduits and wiring to be abandoned in place 2-inches (50-mm) below the surface of the adjacent construction, cap the conduit end, and patch the surface to match the existing finish. The Contractor shall cut existing conduits installed in concrete slabs to be abandoned in place flush with the top of the slab and fill conduit end with a minimum of 4-inches (100-mm) of concrete.

#### **M. Patching and Repairing:**

The Contractor shall comply with Article 1.20-1.08.03 subsection 3H for patching and repairing damage to adjacent construction caused by selective demolition operations.

**N. Disposal of Demolished Materials:**

The Contractor shall (1) not allow demolished materials to accumulate or be sold on the Project Site; (2) not burn demolished materials on the Project Site; and (3) promptly and legally dispose or recycle demolished materials off the Project Site.”

**1.20-1.08.05--Workmen and Equipment:**

*Replace “FM with “FMG” in subsection (a)*

**1.20-1.08.14--Acceptance of Project:**

*Add the following to subsection 2 under the heading “Equipment and Systems Maintenance Manual:”*

“(j) Copies of maintenance agreements with service agent name and telephone number.”

*Add the following to subsection 3 after the last paragraph:*

“The Contractor shall video record each training session and provide said video to the Engineer for the owner’s future use.”

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 3.04  
PROCESSED AGGREGATE BASE**

*Delete the entire Section and replace with the following:*

**3.04.01--Description:** The base shall consist of a foundation constructed on the prepared subbase or subgrade in accordance with these specifications and in conformity with the lines, grades, compacted thickness and typical cross-section as shown on the plans.

**3.04.02--Materials:** All materials for this work shall conform to the requirements of Article M.05.01.

**3.04.03--Construction Methods:** Only one type of coarse aggregate shall be used on a project unless otherwise permitted by the Engineer.

Prior to placing the processed aggregate base, the prepared subbase or subgrade shall be maintained true to line and grade, for a minimum distance of 200 feet (60 meters) in advance of the work. None of the aggregate courses shall be placed more than 500 feet (150 meters) ahead of the compaction and binding operation on that particular course.

The processed aggregate base shall be spread uniformly by a method approved by the Engineer. The thickness of each course shall not be more than 4 inches (100 millimeters) after compaction, unless otherwise ordered.

After the aggregate is spread, it shall be thoroughly compacted and bound by use of equipment specifically manufactured for that purpose. Rollers shall deliver a ground pressure of not less than 300 pounds per lineal inch (52.5 newtons/millimeter) of contact width and shall have a weight (mass) not less than 10 tons (9100 kilograms). Vibratory units shall have a static weight (mass) of not less than 4 tons (3650 kilograms). Water may be used during the compaction and binding operation and shall be applied from an approved watering device. The compacting and binding operation shall begin at the outside edges, overlapping the shoulders for a distance of not less than 6 inches (150 millimeters) and progress towards the middle, parallel with the centerline of the pavement. The work shall cover the entire surface of the course with uniform overlapping of each preceding track or pass. Areas of super-elevation and special cross slope shall be compacted by beginning at the lowest edge and proceeding towards the higher edge, unless otherwise directed by the Engineer. The compacting and binding operation shall be continued until the voids in the aggregates have been reduced to provide a firm and uniform surface satisfactory to the Engineer. The amount of compactive effort shall in no case shall be less than four (4) complete passes of the compacting and binding operations. All aggregate shall be completely compacted and bound at the end of each day's work or when traffic is to be permitted to operate on the

road. The dry density of each layer of processed aggregate base after compaction shall not be less than 95 percent of the dry density for that material when tested in accordance with AASHTO T180, Method D.

Should the subbase or subgrade material become churned up or mixed with the processed aggregate base at any time, the Contractor shall, without additional compensation remove the mixture. The Contractor shall add new subbase material, if required, and reshape and recompact the subbase in accordance with the requirements of Article 2.12.03. New aggregate material shall be added, compacted and bound, as hereinbefore specified, to match the surrounding surface.

Any surface irregularities which develop during, or after work on each course, shall be corrected by loosening material already in place and removing or adding aggregate as required. The entire area, including the surrounding surface, shall be re-compact and rebound until it is brought to a firm and uniform surface satisfactory to the Engineer.

**3.04.04--Method of Measurement:** Processed Aggregate Base will be measured horizontally in-place after final grading and compaction. Materials placed beyond the horizontal limits indicated on the plans will not be measured for payment.

The total thickness shall be as indicated on the plans, or as ordered by the Engineer and within a tolerance of minus three-fourths of an inch ( $-\frac{3}{4}$ " ) to plus one-half inch ( $+\frac{1}{2}$ " ) (-19 millimeters to +13 millimeters).

Measurements to determine the thickness will be taken by the Engineer at intervals of 500 feet (150 meters) or less, along lanes, and shall be considered representative of the lane. For the purpose of these measurements, a shoulder will be considered a lane.

If a thickness measurement is taken and found deficient, the Engineer will take such additional measurements as he considers necessary to determine the longitudinal limits of the deficiency. Areas not within allowable tolerances shall be corrected, as ordered by the Engineer, without additional compensation to the Contractor.

**3.04.05--Basis of Payment:** This work will be paid for at the contract unit price per cubic yard for "Processed Aggregate Base", complete in place, which price shall include all materials, tools, equipment and work incidental thereto.

Pay Item	Pay Unit
Processed Aggregate Base	c.y. (cu. m)



**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 4.01  
CONCRETE PAVEMENT**

**Article 4.01.03-A. Composition:**

*Add the following new paragraph before the last paragraph:*

“The temperature of the concrete at the time of placement shall not be less than 60° F (15.5° C) or greater than 90° F (32° C). For pumped concrete, the temperature shall be determined at the placement end of the pump line. The temperature of the concrete shall be determined in accordance with ASTM C1064.”

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 6.01  
CONCRETE FOR STRUCTURES**

**Article 6.01.03-8. Placing Concrete:**

*Add the following new paragraph after the first paragraph:*

“The temperature of the concrete at the time of placement shall not be less than 60° F (15.5° C) or greater than 90° F (32° C). For pumped concrete, the temperature shall be determined at the placement end of the pump line. The temperature of the concrete shall be determined in accordance with ASTM C1064.”

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 6.03  
STRUCTURAL STEEL**

**6.03.03 – Construction Methods:**

*In the 5<sup>th</sup> paragraph of subsection 37 Shop Painting, replace “MS MIL” with “MILSPEC.”*

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 6.12  
CONCRETE CYLINDER CURING BOX**

*Delete the entire section and replace with it the following:*

**6.12.01 –Description:** This item shall consist of furnishing a box for curing concrete test cylinders. The box shall be commercially available and manufactured specifically for curing concrete test cylinders. The box will remain the property of the Contractor at the conclusion of the project. The box shall be delivered to a location on the project as directed by the Engineer.

**6.12.02 – Materials:** A catalog cut listing detailed specifications of the box and operating instructions from the manufacturer must be submitted to the Engineer. The box and its components shall be constructed of non-corroding materials and shall be capable of storing a minimum of 18 test cylinders, 6" X 12" (152 mm X 305 mm) stored vertically with the lid closed. The lid must be watertight when closed and hinged in the back with security latches on the front that can be padlocked. The box must be capable of holding water to a maximum level of one inch above test cylinders placed in the box vertically. A drain hole must be provided in a wall of the box to allow manual drainage of the water that exceeds this level. A drain hole must also be provided at the bottom of the box so that it can be manually emptied. The temperature of the water must be controlled by heating and cooling device capable of maintaining the temperature of the water within a range of 60 to 80° F, +/- 2 °F (15.5 to 26.7 °C, +/- 1 °C) within an outside ambient air temperature range of -10 to 120 ° F (-23.3 to 49 °C). The heating and cooling device must be positioned to allow free circulation of air and water around the cylinders and be rated at 120 volts and 15 amps. A rack must be provided within the box to support the cylinders above the pool of temperature controlled water. The device must be thermostatically controlled with a digital readout that is capable of displaying the high/low water temperature within the box since the last reading was taken.

**6.12.03 - Construction Methods:** The Contractor shall maintain the curing box in working order and shall provide all necessary electrical service and water so that the curing box can be used properly during the entire course of the project. Any curing box that is not operating properly, as determined by the Engineer, shall be replaced within 24 hours by the Contractor at no expense to the State. The Engineer reserves the right to prohibit placement of fresh concrete on the project until a curing box acceptable to the Engineer is operational on the project site.

**6.12.04 - Method of Measurement:** The furnishing of the concrete test cylinder curing box will be measured for payment by the number of boxes delivered by the Contractor and accepted by the Engineer.

**6.12.05 – Basis of Payment:** This item will be paid for at the contract unit price each for “Concrete Cylinder Curing Box” ordered and accepted on the project, which price shall include all submittals, material, tools, equipment, and labor incidental thereto. The price shall also include all maintenance and operating costs related to the curing box for the duration of the project.

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 7.02  
PILES**

**Article 7.02.05- Basis of Payment:**

In the first sentence of the first paragraph of Section "2. Timber Piles" change "Furnishing Timber Piles Foot (Meter Length) and Furnishing Treated Timber Piles Foot (Meter Length)" to "Furnishing (Type) Timber Piles (Foot (Meter) Length)".

In the first sentence of the last paragraph of Section "2. Timber Piles" change "Driving Timber Piles" and "Driving Treated Timber Piles " to "Driving (Type) Timber Piles".

*Under Pay Items:*

*Delete:*

<u>Pay Item</u>	<u>Pay Unit</u>
Furnishing (Type) Piles (Lengths)	lb. (kg)

*Add:*

<u>Pay Item</u>	<u>Pay Unit</u>
Furnishing (Type) Timber Piles (Length)	ea. (ea)
Furnishing Steel Piles	lb. (kg)
Furnishing (Type) Prestressed Concrete Piles	l.f. (m)
Cast-in-Place Concrete Piles	l.f. (m)

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 9.10  
METAL BEAM RAIL**

**Article 9.10.04 – Method of Measurement**

**Subarticle 1 – Metal Beam Rail (Type)**

*Delete the only sentence and replace with the following:*

The length of metal beam rail measured for payment will be the number of linear feet (meters) of accepted rail of the type or designation installed, including radius rail other than Curved Guide Rail Treatment, measured along the top of rail between centers of end posts in each continuous section.

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 9.18  
THREE CABLE GUIDE RAILING  
(I-BEAM POSTS) AND ANCHORAGES**

**9.18.03 – Construction Methods:**

*In the 10<sup>th</sup> paragraph, replace “MIL” with “MILSPEC.”*



**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 10.10  
CONCRETE HANDHOLE**

**Article 10.10.05 – Basis of Payment**

*Remove the words “ground wire”.*

*At the end of the paragraph add the following sentence:*

The ground wire (bonding wire) is included in the Contract unit price under Section 10.08 – Electrical Conduit.

*Add the word “Cover” to the end of the pay item “Cast Iron Handhole”*

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION 11.13  
CONTROL CABLE**

**11.13.03 – Construction Methods:**

*In the 1st paragraph of subsection 2 replace "MIL" with "MILSPEC."*

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION M.16  
TRAFFIC CONTROL SIGNALS**

**Article M.16.04 – Poles:**

**Subarticle 1. Steel Poles:**

(i) Wire Entrance Fitting:

*In the second sentence, delete “required to accept the cables”.*

**Article M.16.06 – Traffic Signals:**

*In the 1st paragraph of subsection 9 replace “MIL” with “MILSPEC” and under “Third Coat” replace “MIL” with “MILSPEC.”*

**Article M.16.08 – Pedestrian Push Button**

**Subarticle – Painting**

*Delete the entire “Third Coat” paragraph and replace with the following:*

**Third Coat:** Dark Green Enamel, shall be DARK GREEN exterior-baking enamel and shall comply with Federal Specifications A-A 2962. The color shall be No. 14056, Federal Standard No. 595.

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION M.17  
ELASTOMERIC MATERIALS**

**M.17.01 – Elastomeric Bearing Pads:**

*In the 2nd paragraph of subsection 4(b), replace “MS MIL” with “MILSPEC.”*

**CONNECTICUT  
SUPPLEMENTAL SPECIFICATION  
SECTION M.18  
SIGNING**

**M.18.10 – Demountable Copy:**

*In the chart under subsection 3H, replace “MS MIL” with “MILSPEC.”*